

LEASE NAME Hueftle

WELL NUMBER 5

4290 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 28 TWP. 12S RGE. 33W or (W)

COUNTY Logan

Date Well Completed 8/14/97

Plugging Commenced 11:00PM 8/13/97

Plugging Completed 2:15AM 8/14/97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR THE DANE G. HANSEN TRUST

ADDRESS P.O. Box 187 Logan, Kansas 67646

PHONE (785) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/13/97

by Dennis Hamel

(KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom _____ T.O. 4681

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	330	8 5/8	330.18	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
1st Plug @ 2640' w/25sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes with 51 Vis Mud.
2nd Plug @ 1580' w/100sks 15sks In Rat Hole Displaced Plugs with mud.
3rd Plug @ 380' w/40sks 200sks 60/40 Poz 6% Col w/1#FS/sk By Allied cementing
4th Plug @ 40' w/10sks Completed @ 2:15AM 8/14/97

Name of Plugging Contractor DISCOVERY DRILLING, INC. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales (Employee of Operator) or (~~OWNER~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Dane G. Bales
(Address) P.O. Box 187, Logan, KS 67646



SUBSCRIBED AND SWORN TO before me this 4th day of September, 19 97

Betty Jane Bittel
Notary Public

My Commission Expires: July 17, 2000.

USE ONLY ONE SIDE OF EACH FORM

Rec'd
09-05-1997