

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-109-20,545-00-00

LEASE NAME Bob Clark

WELL NUMBER #1

3300' Ft. from S Section Line

1980' Ft. from E Section Line

SEC. 26 TWP. 12S RGE 33 (E) or (W)

COUNTY Logan

Date Well Completed \_\_\_\_\_

Plugging Commenced 12-20-92

Plugging Completed 12-20-92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Olympic Petroleum Company

ADDRESS 2121 S. Columbia Ave, Tulsa, OK 74114

PHONE# (918) 747-8091 OPERATORS LICENSE NO. 5248

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-20-92 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top \_\_\_\_\_ Bottom T.D. 4725'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Su				8 5/8"	305'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Fill w/heavy mud; set 1st plug @ 2590'-2490' w/25 sx; 2nd plug @ 1525'-1125' w/100 sx;  
3rd plug @ 340'-180' w/40 sx; 4th plug @ 40'-surface w/10 sx w/wiper plug. Total 190 sx;  
60-40 posmix 1/4# Flocel per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Olympic Petroleum Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) of \_\_\_\_\_

above-described well, being first duly sworn on oath, says: That I have knowledge of the \_\_\_\_\_ statements, and matters herein contained and the log of the above-described well \_\_\_\_\_ the same are true and correct, so help me God.




(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202

RECEIVED of STATE CORPORATION COMMISSION  
JAN 19 1993  
CONSOLIDATION DIVISION  
WICHITA, KANSAS

SUBSCRIBED AND SWORN TO before me this 15th day of January, 19 93



Angela Kardard  
Notary Public

My Commission Expires: March 20, 1993