

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Conservation Agent's Report

PCND
KCC
11-15-73

Operator's Full Name R. B. Asher

Complete Address 9812 Shade, Wichita, Kansas 67212

Lease Name F. J. Barkman Well No. 1

Location C W/2 NE NE Sec. 31 Twp. 32 Rge. 6E (E) (W)

County Cowley Total Depth 3130'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Voth Casing Pulling

Address 715 South A, Arkansas City, Kansas License No. 684

Operation Completed: Hour Day 17 Month 11 Year 1973

The above well was plugged as follows:

150' - 8-5/8" Pb. 2000' Top perf. 1896' - 5-1/2"

Pushed plug to 1850', put in 5' sand and dumped 5 sacks cement

with dump bailer. Pulled casing and pushed plug to 200'.

Put in 10' rock bridge and filled to top with 4 yards ready

mix cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Eugene P. [Signature]
Well Plugging Supervisor

11/15/73
INV. NO. 6050-E