

AUG 15 1973

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1973
08-15-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-109-20025-00-00

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Medford Well No. 1

Location CNE-SE Sec. 7 Twp. 12 Rge. (E) (W) 36

County Logan Total Depth 1470'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 8:30 PM Day 11 Month 8 Year 1973

The above well was plugged as follows:

169'--8 5/8" Surface casing, cement circulated with 135 Sx.
Top of Dakota section @ 1250'.

Circulated hole with heavy mud. Pulled DP to 1475' and displaced 110 Cu. Ft. cement
thru DP from 1475' to 1150'. Pulled DP to 180' and displaced 30 Cu. Ft. cement thru
DP from 180' to 105'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. D. Dicks
Well Plugging Supervisor

INVOICED
DATE 8/15/73
INV. NO. 7773-u