

LEASE NAME Berardo

WELL NUMBER #1

3960 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 3 TWP. 10 RGE. 33 (W)

COUNTY Thomas

Date Well Completed 3-14-77

Plugging Commenced 5-23-94

Plugging Completed 5-23-94

RECEIVED

6-17-94
JUN 17 1994

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Brito Oil Company, Inc.

ADDRESS 120 S. Market, Suite 300, Wichita, KS 67202

PHONE# (316) 263-8787 OPERATORS LICENSE NO. 4629

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Feb. 14, 1994 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Lansing/Marm Depth to Top 4202 Bottom 4600 T.D. 4744

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From Surf | To | Size | Put in | Pulled out |
|---------------------|----------------|-----------|-------------|---------------|-------------|---------------------|
| <u>LLC 4202-58'</u> | <u>Oil/Wtr</u> | | <u>4725</u> | <u>4 1/2"</u> | <u>3/77</u> | <u>Left in hole</u> |
| <u>LKC 4312-16'</u> | <u>Oil/wtr</u> | | | | | |
| <u>Cherokee</u> | <u>Oil/Wtr</u> | | | | | |
| <u>4590-4600'</u> | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set Mix 50 SX (65/35 Posmix, 10%gel) dwn back side. Press to 200#, shut in. Mix 60 SX dwn 2" tbq & displace. Mix 100 sx dwn 2" tbq and circ. to surface. Had perf. csq @ 1700' w/ 1 shot.

Name of Plugging Contractor Poe Servicing License No. 3152

Address Box 115, Oberlin, KS 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brito Oil Company, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

Raul F. Brito, President

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 120 S. Market Suite 300
Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 17 day of June, 19 94

[Signature]
Notary Public

My Commission Expires: 9-28-97

USE ONLY ONE SIDE OF EACH FORM