

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-193-20,131 - 00-00

LEASE NAME Berardo A

WELL NUMBER #3

2970'
990'
Ft. from S Section Line
Ft. from E Section Line

SEC. 3 TWP. 10S RGE. 33W (E) or (W)

COUNTY Thomas

Date Well Completed 5/16/77

Plugging Commenced 10/4/01

Plugging Completed 10/5/01

RECEIVED
NOV 08 2001
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226

PHONE # (316) 682-1537 OPERATOR'S LICENSE NO. 5030

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09/29/2001 (date)
by Bruce Bayse (KCC District Agent's Name)

Is ACO-1 filed? no If not, is well log attached? NA

Producing Formation LKC Depth to Top 4096' Bottom 4238' T.D. 4746'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	415'	-----
				4-1/2"	4746'	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Perforated at 465', 1950', 2640'. Ran tubing to 3750' and spotted 70 sx 60/40 poz w/10% gel and 200# hulls.

Pulled to 2400' and spotted 70' sx cement w/200# hulls. Pulled to 900' and spotted 70 sx cement w/200# hulls and cement circulated

Pulled tubing. Tied onto casing and pumped 30 sx cement and pressured to 500#. SI.

Tied onto braden head and pumped 60 sx cement. Press. to 100# and SI. Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Joe Rupp License No. _____

Address 1019 S. Pennsylvania Avenue, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

W.R. Horgan (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says that: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

8100 E. 22nd St. N., Bldg. 300
Wichita, KS 67226

(Address)

SUBSCRIBED AND SWORN TO before me this 2ND day of November 2001

My Commission Expires:



Notary Public

Form CP-4
Revised 05-88

CR



CHARGE TO: Vess Oil Corp
 ADDRESS:
 CITY, STATE, ZIP CODE:

TICKET No 3843

PAGE 1 OF 1

1. SERVICE LOCATIONS <u>Ness City</u>	WELL/PROJECT NO. <u>A-3</u>	LEASE <u>Berado</u>	COUNTY/PARISH <u>Thomas</u>	STATE <u>KS</u>	CITY	DATE <u>10-5-01</u>	OWNER <u>Same</u>
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR	RIG NAME/NO. <u>Cheyenne</u>	SHIPPED VIA <u>105</u>	DELIVERED TO <u>N.W. Oaklev</u>	ORDER NO.	
3.	WELL TYPE <u>61L</u>	WELL CATEGORY <u>Abandoned</u>	JOB PURPOSE <u>P.T.A.</u>	WELL PERMIT NO.	WELL LOCATION		
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575					MILEAGE	60	mi			2.50	150.00
576					Pump charge	1	EA				500.00
275					Hulls	6	SKS			22.00	132.00
329					60/40 10% Gel	300	SKS			5.85	1755.00
581					Bulk service charge	300				1.00	300.00
583					Drayage	816	30	T.M.		.75	612.23
RECEIVED											
NOV 08 2001											
KCC WICHITA											

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X Joe Rupp
 DATE SIGNED 10-5-01 TIME SIGNED 1:00 A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	3449	23
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?						
WE UNDERSTOOD AND MET YOUR NEEDS?						
OUR SERVICE WAS PERFORMED WITHOUT DELAY?						
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	169	01
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	3618	24
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND						

JOB LOG

SWIFT Services, Inc.

DATE 10-5-01 PAGE NO.

CUSTOMER **Vess OIL CORP.** WELL NO. **A-3** LEASE **Berado** JOB TYPE **P.T.A.** TICKET NO. **3843**

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1230							on loc wait on Rig Crew + Tbg
70	1530		25					Perfs AT 465, 1950, 2640 Tbg at 4000 ³⁷⁰⁰ SPOT 70SKS 60/40 10% Gel w/ 200# hulls
70	1550							Pull Tbg to 2400'
70	1620		25					SPOT 70 SKS CMT w/ 200# hulls at 2400'
	1630							Pull Tbg to 900'
70	1710		25					Pump 70SKS Cement w/ 200# hulls at 900' Circ CMT to SURF
	1725							pull Tbg out of Hole
30								Hook up To 4 1/2 + Pump 30 SKS CMT PSI to 500 + shut in
30			11					Hook up to 8 5/8 + Pump 30 SKS CMT 8 5/8 on VAC.
30								Pump 30 SKS CMT PSI to 100 on 8 5/8
	1830							Job Complete
								4 1/2 - 240 SKS CMT 600# Hulls
								8 5/8 60 SKS CMT

RECEIVED
NOV 08 2001
KCC WICHITA