

LEASE NAME Van Vliet

WELL NUMBER A-1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

3630 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 3 TWP. 10 RGE. 33 (X) or (W)

COUNTY Thomas

LEASE OPERATOR Buffalo Operating LLC

ADDRESS 1720 S Bellaire Denver, CO 80222

Date Well Completed 8/77

PHONE# (303) 757-8431 OPERATORS LICENSE NO. 31653

Plugging Commenced 9/8/95

Character of Well Oil

Plugging Completed 9/8/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/7/95 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? ye s If not, is well log attached? _____

Producing Formation LKC Depth to Top 4253 Bottom 4275 **RECEIVED** 4800

STATE CORPORATION COMMISSION

9-18-95

SEP 18 1995

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Put Out	CONSERVATION DIVISION Wichita, Kansas
Johnson	Oil	4609	4615	8 5/8	401	0	
LKC	Oil	4101	4336	4 1/2	4773	0	
Toronto	Salt Water	4047	4052				
Heebner	Salt Water	4028	4050				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Set 75 sx plug at 3786', set 75 sx plug w/500# hulls at 2100',
circulate 25 sx from 1000' to surface Pump 50 syx of cement down
surface-production casing annulus.

-All cement was 60/40 Poz-mix w/ 10% gel -

Name of Plugging Contractor Poe Well Service License No. 3152

Address PO Box 115 Oberlin, KS 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Buffalo Operating LLC

STATE OF Colorado COUNTY OF Denver, ss.


Randall K. Arnold

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed the
the same are true and correct, so help me God.

(Signature) Randall K. Arnold

(Address) 1720 S Bellarie Denver, CO 80222



SUBSCRIBED AND SWORN TO before me this 15th day of September, 19 95

Debby J. Black
Notary Public

My Commission Expires:

USE ONLY ONE SIDE OF EACH FORM