

15-109-20025-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Logan County, Sec. 7 Twp. 12 Rge. 36 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C NE SE
Lease Owner Dreiling Oil, Inc.
Lease Name Medford Well No. 1
Office Address Rt. #2, Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-11 19 73
Application for plugging filed 8-11 19 73
Application for plugging approved 8-11 19 73
Plugging commenced 8-11 19 73
Plugging completed 8-11 19 73
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Morland, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4,707 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	169'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug was set @ 1,475' w/110 cu. ft. cement
2nd plug was set @ 180' w/30 cu. ft. cement
3rd plug was set @ 40' w/10 cu. ft. cement

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1973
08-16-1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Dreiling Oil, Inc.
Address Rt. #2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Joe Hess, Sec. Treas. of Drlg. Contr. (employee of owner or contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe Hess
JOE HESS, Rt. #2, Victoria, Kansas 67671
(Address)

Subscribed and sworn to before me this 15th day of August, 1973
Cecilia Basgall
Cecilia Basgall Notary Public.

My commission expires September 13, 1976.



Locate well correctly on above Section Plat



DREILING OIL, INC.

Victoria, Kansas 67671

15-109-20025-00-00

Dreiling Oil, Inc.		WELL LOG		
Company	Rt. #2 Victoria, Kansas 67671	Sec. 7	Twp. 12	Rng. 36
Farm	Medford No. 1	Location	C NE SE	
Total Depth	4,707'	County	Logan	
Comm.	7-30-73	Comp.	8-10-73	Elevation: 3124 K. B.
Contractor	Dreiling Oil, Inc.		3121	D. F.
	Rt. #2			
	Victoria, Kansas 67671		3119	G. R.

Casing Record	Cement Record	Production:
169' - 8 5/8"	135 sacks cement	D & A

Figures Indicate Bottom of Formations

0'	25'	Top Soil
25'	169'	Shale
169'	1754'	Shale
1754'	1816'	Hard Sand
1816'	1900'	Shale
1900'	1960'	Blain Anhydrite
1960'	2160'	Shale and Sand
2160'	2691'	Shale
2691'	2731'	Anhydrite
2731'	2805'	Shale & Hard Sand
2805'	3485'	Shale and Lime
3485'	3795'	Lime
3795'	3895'	Lime & Shale
3895'	4665'	Lime
4665'	4707'	Miss.
4707'	T.D.	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 10 1973
 08-16-1973
 CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Joe Hess, Secretary Treasurer, of Dreiling Oil, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Medford #1.

Joe Hess
 JOE HESS

Subscribed and sworn to before me this 15th day of August, 1973.

Cecilia Basgall
 Cecilia Basgall Notary Public



My commission expires September 13, 1976.