

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-199-20205-00-00

API NUMBER ~~15-199-30,205-00-00~~

LEASE NAME Burk

WELL NUMBER 23-1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 23 TWP. 12S RGE. 41 / VEY (W)

COUNTY Wallace

LEASE OPERATOR Holden Energy Corporation

ADDRESS Lincoln Center, Suite #600, Ardmore, OK 73401

PHONE# (405) -226-3960 OPERATORS LICENSE NO. 30575

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 11/16/91

Plugging Commenced 11/16/91

Plugging Completed 11/16/91

The plugging proposal was approved on 11-16-91 (date)

by Gilbert Scheck (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5240'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled
				8-5/8"	271'	-0-

NOV 20 1991  
11-20-1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 5240'-2850'	10 sks cement @ 40'
25 sks cement @ 2850'	15 sks in rathole
100 sks cement @ 1475'	10 sks in mousehole
40 sks cement @ 300'	

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Holden Energy Corporation

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Kyle B. Branum  
Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 10th day of November, 19 91

GLEND A R. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-92

[Signature]  
Glenda R. Tiffin, Notary Public

My Commission Expires: 2-6-92

15-199 - 20205 - 00-00-00

RECEIVED  
STATE CORPORATION COMMISSION

NOV 20 1991  
11-20-1991

EMPHASIS OIL OPERATIONS

P. O. BOX 506  
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Holden Energy Corporation  
Lincoln Center, Suite #600  
Ardmore, OK 73401

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Burk

WELL #23-1

LOCATION: SW NE  
Section 23-12S-41W  
Wallace County, Kansas

LOGGERS TOTAL DEPTH: 5232'

ROTARY TOTAL DEPTH: 5240'

COMMENCED: 11/7/91

CASING: 8-5/8" @ 271' w/160 sks cement

ELEVATION: 3621' K.B.

COMPLETED: 11/16/91

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Shale	90'	Lime	4635'
Stone Corral	2871'	Shale	4740'
Sand & Shale	2894'	Morrow	4951'
Shale	3590'	Mississippi	5071'
Shale & Lime	4585'	R.T.D.	5240'


STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)

Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
\_\_\_\_\_  
Kyle B. Branum

Subscribed and sworn to before me on November 19, 1991.

My commission expires: February 6, 1992.

  
\_\_\_\_\_  
Glenda R. Tiffin, Notary Public

