


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Wallace County. Sec. 27 Twp. 12S Rge. (E) 41 (W)

Location as "NE/CNW%SW%" or footage from lines SW SE

Lease Owner Arvel C. Smith & Toto Gas Company

Lease Name Burk Well No. 1

Office Address 814 North Mission, Wichita 6, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 30, 1962

Application for plugging filed " " 19 "

Application for plugging approved " " 19 "

Plugging commenced " " 19 "

Plugging completed " " 19 "

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 5238 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Pipe	0	236'	8 5/8"		No

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- 0 - 30' Ten sack cement plug
- 30'- 206' Heavy Mud
- 206'- 265' Twenty sack cement plug
- 265'- T.D. Heavy Mud

12-03-1962
1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Natural Gas Drilling, Inc.

Address Fox 1615, Oklahoma City, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Arvel C. Smith (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arvel C. Smith
814 North Mission, Wichita 6, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of November, 1962

Beverly Ryan
Notary Public.

My commission expires September 30, 1964

15-199-00005-00-00

DRILLERS LOG

NO. 1 BURK
SW SE Sec. 27-12S-41W
Wallace County, Kansas

Commenced November 10, 1962

Completed November 29, 1962 - Dry and Abandoned.

8 5/8" surface casing set at 236 feet, cemented with 250 sacks of cement; circulated to surface.

Formation Record:

0 - 750'	Shale
750 - 1520'	Sand, shaley
1520 - 2930'	Shale and sand
2930 - 3600'	Anhydrite, sand and shale
3600 - 5040'	Lime, chalky lime, shale streaks
5040 - 5120'	Shale with lime streaks
5120 - 5175'	Lime, chalky
5175 - 5200'	Sand
5200 - 5230'	Lime and Chert
5230'	Total Depth

Hole filled with heavy mud; 20 sack cement plug set 265' to 206' thru drill pipe; Heavy mud 206' to 30'; 10 sack cement plug 30' to surface.

I hereby certify that the above and foregoing is a true and accurate report of the drilling and abandonment of the well described.

Dated November 30, 1962.

E. Howard

Subscribed and sworn to before me, a Notary Public, this 30th day of November, 1962.

Louis B. Reid
Notary Public

Plugging Inspector: Eldon Petty
Hays, Kansas