

4-031930

5-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,121-0000

C NE /4 SEC. 03, 10 S, 33 W
3960 feet from S section line
1320 feet from E section line

Operator license# 4629

Lease Berado well # 1

Operator: Brito Oil Company, Inc.

County Thomas

Address: 200 E. First
Suite 208
Wichita, Kansas 67202

Well total depth 4744 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 337 feet

154.75

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Poe Well Service License# 3152

Address: Oakley, Kansas 67748

Company to plug at: Hour: P.M. Day: 23 Month: May Year: 94

Plugging proposal received from: Paul Brito

Company: Brito Oil Company, Inc. Phone: _____

Were: Order 210 sxs. 65/35 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 1:30P.M., Day: 23, Month: May, Year: 94

Actual plugging report: 8 5/8" set @ 337' w/225 sxs. cwc. 4 1/2" set @ 4725' w/225 sxs. Prod. perfs 4202' - 4600'. Ran wireline to bottom - tag sand at 2700' - critical area shot at 1700'. Ran tubing to 2500' circulated cement blend slurry to surface. Squeezed 4 1/2" with total 160 sxs. cement blend with 500# hulls mixed in. Squeezed 8 5/8" with 50 sxs. cement blend to Max. P.S.I. 200#. Close in P.S.I. 200#. Plug complete.

RECEIVED
JUN 03 1994
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did / did not [] observe the plugging. Carl Goodrow

(agent)

Form CP-2/3

6-6-94
40535
5-23

FD