

4-032181

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

10-14

API Number: 15-193-20,128 -0000

W2 W2 NE /4 SEC. 03, 10, 33 W
3960 feet from S section line
2310 feet from E section line

Operator license# 4629

Lease: Brito "A" Well # 2

Operator: Brito Oil Company, Inc.

County: Thomas 155.15

Address: 120 S. Market - Suite #300
Wichita, Kansas 67202

Well total depth 4774 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 410 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Poe Servicing License# 3152

Address: Oberlin, Kansas 67749

Company to plug at: Hour: P.M. Day: 14 Month: October Year: 1996

Plugging proposal received from: Paul Brito

Company: Brito Oil Company, Inc. Phone:

Were: Order 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

10-25-96

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 2:00 P.M., Day: 14, Month: October, Year: 1996

Actual plugging report: 8 5/8" set at 410' w/250 sxs cwc. 4 1/2" set at 4774' with 225 sxs.
Critical area control shot at 1700'. Prod. perms 4101' - 4612'. PBSD 4720'. Squeezed
4 1/2" with 100 sxs cement with 500# hulls mixed into Max. P.S.I. 300#. Blew out casing.
Squeezed 8 5/8" with 50 sxs cement to Max. P.S.I. 150#. Held. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [] / did not [X] observe the plugging.

Carl Goodrow (agent)

Form CP-2/3

10-25-96

46818