

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-193-20131-00-00  
Spot: CSWSENE Sec/Twnshp/Rge: 3-10S-33W  
2970 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: BERARDO A Well Number: 3  
County: THOMAS Total Vertical Depth: 4746 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 415 250 SX CMT 8154.25  
Production: Size 4.5 feet: 4727 225 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/05/2001 3:30 PM  
Plug Co. License No.: 5030 Plug Co. Name: VESS OIL CORPORATION  
Proposal Rcvd. from: PAT CANADAY Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Order 300 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Plugging Plug through tubing.  
Method:

Plugging Proposal Received By: BRUCE BASYE WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 10/05/2001 6:30 PM KCC Agent: HERB DEINES

**Actual Plugging Report:**


8 5/8" to 415' w/250 sxs. 4 1/2" to 4727' w/225 sxs.  
Perforated casing at 465' - 1950' - 2650'.  
Ran tubing to 3700' and pumped 70 sxs cement with 200# hulls.  
Pulled tubing to 2400' and pumped 70 sxs cement with 200# hulls.  
Pulled tubing to 900' and pumped 70 sxs cement with 200# hulls with cement to surface.  
Pulled tubing and tied onto production casing.  
Pumped 30 sxs cement and pressured to 500#.  
Tied onto annulus and pumped 60 sxs cement.  
Max. P.S.I. 100#.

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

RECEIVED

1-18-2002

JAN 18 2002

KCC WICHITA

JAN 16 2002

INVOICED

DATE

Jan 23, 02

INV. NO.

2002061281

DONALD C. SLAWSON & BRUCE ANDERSON #3 BERARDO "A" 3-10-33W SW SE NE  
 218 223 BLDG., WICHITA, KS.  
 CONTR SLAWSON DRILG. CO., INC. CITY THOMAS  
 GEOL GEORGE MUELLER FIELD REEARDO

E 311E KB CM 4/13/77 CARD ISSUED 7/28/77 IP P 150 BOPD + TR WTR  
 CHER 4587-4600

API 15-193-20,131

LOG	TOPS	DEPTH	DATUM	
ANH		2628	+ 490	
E ANH		2656	+ 462	
HEEB		4007	- 889	DST (1) 4015-4048/30-45-45-60, 110' MSW
TOR		4029	- 911	40' M W/SP OIL, SIP 1100-1025# FP
LANS		4048	- 930	37-75# 75-131#
STV		4264	-1146	DST (2) 4070-4110/PKR FAILED
BKC		4323	-1205	DST (3) 4068-4110/30-45-45-60, 123' CO
MARM		4352	-1234	(GR 29°) 126' MO, 126' OCM, N/W, SIP
PAWN		4454	-1336	1306-1306# FP 37-84# 93-177#
L CHER		4540	-1422	DST (4) 4125-35/30-45-45-60, 45' CO (GR
JH ZN		4585	-1467	31°) 63' MO, SIP 1268-1250# FP 28-
E CHER SD		4626	-1508	37# 56-56#
MISS		4640	-1522	DST (5) 4176-4220/30-45-45-60, 1330' SW
MISS ?		4646	-1528	W/SC OIL, SIP 1294-1294# FP 47-307#
LTD		4730	-1612	317-605#
RTD		4746	-1628	DST (6) 4219-4250/30-45-45-60, 1450' GIP
				1950' CO, SIP 1250-1250# FP 56-373#
				(OVER)

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

DONALD C. SLAWSON & BRUCE ANDERSON #3 BERARDO "A" 3-10-33W SW SE NE

392-690#  
 DST (7) 4258-4277/30-30-30-30, 10' WM, SIP 37-37# FP 19-19# 28-28#  
 DST (8) 4538-4615/30-45-45-60, 525' MO, SIP 745-540# FP 37-186#  
 186-261#  
 MICT - PF (JH ZN) 4587-90 & 4598-4600, AC 3000, SWB 6 BOPH,  
 VOLUME DECLINING, PF 1/4236, 1/4230, 1/4121, 1/4099 (LKC) SWB  
 16 BOPH, NAT, AC 3000, OVERLAP LKC - PF 14/4231-38, 4/4128-30,  
 12/4096-4102, SET BP, DPC - 3 SQZ 4231-38/95SX, RE-PF 4231-38,  
 DOC - 3 SQZ W/98 SX (4096-4102 & 4128-30) SD/ON FU 1250' OIL,  
 N/W, RE-PF 4231-38, SWB 7 1/2 BOPH, N/W, RE-PF 4096-4102, SWB 10  
 BOPH, N/W, AC 250 (4231-38) SWB LD & SWB 28-30 BOPH, SET PKR  
 @ 4554 TO PUMP JOHNSON ZN ONLY, POP