

4-032182

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-193-20,144-0000

10-11

S2 N7  
E2 KCC 32 N2 NW /4 SEC. 03, 10, 33 W  
4795 feet from S section line  
3960 feet from E section line

Operator license# 4629

Lease: Brito "A" Well # 5

Operator: Brito Oil Company, Inc.

County: Thomas 155.35

Address: 120 S. Market - Suite #300  
Wichita, Kansas 67202

Well total depth 4780 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 662 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Poe Servicing License# 3152

Address: Oberlin, Kansas 67749

Company to plug at: Hour: P.M. Day: 11 Month: October Year: 1996

Plugging proposal received from: Paul Brito

Company: Brito Oil Company, Inc. Phone:

Were: Order 225 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Allied Cement Company. 10-25-96  
Order work string.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 11:40 A.M., Day: 11, Month: October, Year: 1996

Actual plugging report: 8 5/8" set at 662' w/300 sxs cwc. 4 1/2" set at 4352' with 125 sxs.  
Critical area control shot at 1700'. Prod. perfs 4264' - 4282'. PBD 4307'. Ran 2 3/8" to 1890'. Spotted 50 sxs cement. Pulled to 880' circulated cement to surface. Lay down pipe, tied onto 4 1/2". Squeezed with total 175 sxs cement blend with 400# hulls mixed in to Max. P.S.I. 500 #. Held. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 200#. Held. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: GL

I did [ ] / did not [ X ] observe the plugging.

Carl Goodrow (agent)

10-25-96  
46817

100.