

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20126-00-00
Spot: N2NWSE Sec/Twnshp/Rge: 3-10S-33W
2200 feet from S Section Line, 2150 feet from E Section Line
Lease/Unit Name: DUMLER H Well Number: 1
County: THOMAS Total Vertical Depth: 4684 feet

Operator License No.: 31253
Op Name: FAGADAU ENERGY CORP.
Address: 4849 GREENVILLE #1600
DALLAS, TX 75206

Production Casing Size: 4.5 feet: 4332 150 sx cmt
Surface Casing Size: 8.62 feet: 374 225 sx cmt

#152^{2.3}

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/07/2003 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE Company: QUALITY WELL SERVICE, INC. Phone: (720) 727-3410

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 600# hulls.
Top down plug through 4 1/2" production casing.
Connect to 8 5/8" surface casing - squeeze with cement.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/07/2003 10:15 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

TD. 4684'. PBTD 4332'. Perfs 4221' - 4225'.
8 5/8" S.P. set at 374' w/225 sxs cement.
4 1/2" production casing set at 4332' w/150 sxs cement.
Connected to 4 1/2" production casing - pumped 225 sxs cement with 600# hulls.
Max. P.S.I. 900#. S.I.P. 200#.
Connected to 8-5/8" surface casing - pumped 80 sxs cement.
Max. P.S.I. 250#. S.I.P. 0#.

RECEIVED
AUG 13 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

102

INVOICED
8-13-03
2004060395

AUG 08 2003

08-12-2003

Barb:
Please send
invoice to:

Operator License No.: 5003
Operator Name: McCoy Petroleum Corporation
Address: P.O. Box 780208
Wichita Kansas 67278-0208

Note:

McCoy Petroleum Corporation
acquired lease on acreage and
discovered an unplugged well
on the lease.
Fagadau Energy Corporation
will not file a T-1.

Sheela
4
Howe Ks

DONALD C. SLAWSON
478 125 BLDG.
WICHITA, KS.
#1 DUMLER "H"
3-10-33W
APPX N/2 NW SE

CONTR SLAWSON DR LG., CO., INC. CITY THOMAS
GEOL GEORGE MUELLER FIELD BERARDO CONF.
E 3.33 XE CM 3/9/77 CARD ISSUED 4/14/77 IP P 180 BOPD + TR W
LKC 4221-25 &
4250-58

API 15-193-22,126

LOG	TOPS	DEPTH	DATUM
AAH		2648	+ 485
HEER		4028	- 895
TCR		4050	- 917
LANS		4068	- 935
STARK		4284	-1151
BKC		4340	-1207
MARM		4370	-1237
...		4478	-1345
L'CHER		4558	-1435
MISS		4670	-1537
RTD		4684	-1551
LTD		4685	-1552

INDEPENDENT OIL & GAS SERVICE

+	+	+
+	+	+
+	+	+

8-5/8" 374/225sx, 4 1/2" 4332/150sx
DST (1) 4195-4235/PKR FAILED
DST (2) 4200-4235/30-45-30-30, 60' OCM
(FO ON TOP) SIP 1352-1315# FP 2 -
37# 46-55#
DST (3) 4132-64/30-45-45-60, 2236' CIR
868' GMO (GR 40°) N/W, SIP 1318-
1300# FP 2-17# 183-311# BHT 120°
DST (4) 4276-4290/30-30-30-30, 1' MO,
SIP 596-49# FP 6-6# 7-7#
DST (5) 4284-4320/30-45-45-60, 450'
SALTY SULF W, SIP 1297-1297# FP
55-128# 128-219# BHT 125°
DST (6) 4560-4637 (W/SP)/30-45-30-30,
20' M, SIP 201-109# FP 36-55# 55-
55# BHT 130°

DONALD C. SLAWSON #1 DUMLER "H" 3-10-33W APPX N/2 NW SE

MICT - PF 1/4223, 1/4249, 1/4256, SWB 9 BOPH, NAT, AC 2500,
PF 8/4221-25 & 16/4250-58, SWB LD + GSO, SWB 48 BOPH + TR W/
2 HRS, POP