

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19219-00-00
Spot: NWNWSENE Sec/Twnshp/Rge: 19-32S-3E
3730 feet from S Section Line, 1075 feet from E Section Line
Lease Name: CARSON Well #: 5B
County: COWLEY Total Vertical Depth: 2737 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.25	2260	354	200 SX
COND	20	36		15 SX
PROD	6.625	2561	354	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/16/2000 8:00 AM
Plug Co. License No.: 33608 Plug Co. Name: W.D. SHORT OIL CO., LLC
Proposal Rcvd. from: MIKE ANSTINE Company: W D SHORT OIL CO LLC Phone: (620) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/20/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2500', CONSOLIDATED MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL, 3% CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2375'. CUT 8.25" CASING @ 354', LAYED DOWN 8-1/4" CASING. CUT 6.625 CASING @ 354', LAYED DOWN 354' OF 6.625 CASING. RIH W/TBG @ 350', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 735 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM, 4-20-2010. CONSOLIDATED CEMENT TICKET #24115.

Perfs:

Top	Bot	Thru	Comments
2710	2737	OH	

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 09 2010


CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)