

#153.73

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20707-00-00
Spot: E2NWNESE Sec/Twnshp/Rge: 24-1S-33W
2310 feet from S Section Line, 915 feet from E Section Line
Lease Name: RATHER A Well #: 1
County: RAWLINS Total Vertical Depth: 4730 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	304	0	190 SX
PROD	4.5	4730	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/04/2010 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: ALAN WANKER Company: DAYSTAR PETROLEUM, INC. Phone: (316) 755-3523

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 4% gel - 600# hulls.
DV Tool at 2928' w/500 sxs cwc.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/04/2010 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Consolidated Oil Well Service pumped 270 sxs 60/40 pozmix - 4% gel with 600# hulls.
Max. P.S.I. 1000#. S.I.P. 800#.
Hooked up to backside and pumped 30 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
4208	4210		LANSING
4202	4204		LANSING
4177	4179		LANSING
4159	4166		LANSING
4101	4105		LANSING
4071			LANSING
4065			LANSING

6/10/10
2010061229

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 09 2010
CONSERVATION DIVISION
WICHITA KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

JUN 07 2010

replacement card

PRESLEY PETROLEUM CO & SOURCE PETROLEUM
WICHITA, KS 67202

24-01 -33W
2310'FSL & 915'FEL, SEC

#1 BATHER "A"

site: 9-1/2 N & 3-3/4 E OF ATWOOD, KS
contr: R & C DRILLING
geol: RANDY LILAK

city: RAWLINS
field: WILHELM

API 15-153-20707

fr date 03/01/88 spd date 03/05/88 drig comp 03/15/88 card issued 05/25/88 last revised 06/28/89

ELV: 3022 KB LOG
 tops.....depth/datum
 OREAD.....3963 -941
 B/OREAD.....3974 -952
 LANS.....4013 -991
 BKC.....4310 -1288
 MISS.....4652 -1630
 ARB.....4678 -1656
 PBDT.....4291 -1269
 RTD.....4730 -1708

IP status:
 OIL, P 25 BO & 5 BWPD, LKC 4065-4105 OA,
 INFO RELEASED: 6/28/89 - WAS OIL WELL - TIGHT HOLE
 CSG: 8-5/8" 304 / 190 SX, 4-1/2" 4730
 NO CORES
 DST (1) 3937-3975 (OREAD), / 30-45-30-45, REC 150'
 MW (45% M, 55% W) ISIP 1283# FSIP 1260# IFP
 109# -109# FFP 135# -135# IHP 2009# FHP 1949# BHT
 117 °
 DST (2) 4024-4075 (LANS 50), / 45-45-60-60, REC 3'
 CLEAN OIL, 122' MW (25% M, 75% W) ISIP 941# FSIP
 884# IFP 82# -82# FFP 113# -82# IHP 2090# FHP
 2007# BHT 119 °

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

PRESLEY PETROLEUM CO & SOURCE PETROLEUM
WICHITA, KS 67202

24-01 -33W
2310'FSL & 915'FEL, SEC

#1 RATHER "A"

DST (3) 4071-4125 (LANS 100), / 30-45-60-60, REC 5' CLEAN OIL, 15' MWCO (60% OIL, 20% W, 20% M), 105' MW (70% W, 30% M) ISIP 941# FSIP 796# IFP 73# -75# FFP 99# -99# IHP 2122# FHP 2078# BHT 120 °
 DST (4) 4125-4170 (LANS 140), / 45-45-60-60, REC 130' DM, W / FEW SPKS OF OIL AT TOP ISIP 658# FSIP 425# IFP 75# -75# FFP 97# -97# IHP 2102# FHP 2049# BHT 120 °
 DST (5) 4168-4220 (LANS 160, 180), / 45-60-45-60, REC 30' DM, NS ISIP 431# FSIP 312# IFP 63# -63# FFP 63# -63# IHP 2159# FHP 2069# BHT 120 °
 MICT - CO, PF (LKC) 4208-4210, 4202-4204, 4177-4179 & 4159-4166, W / 4 SPF, AC 6.5 BBLS (15% MCA) & 7000 GAL (15% SGA), NON-COMMERCIAL, SET BP (DEPTH NA), PF (LKC) 4101-4105, W / 4 SRF & 1 / 4065 & 1 / 4071, AC 3 BBLS (15% MCA) & 750 GAL (15% MCA), GSO, SET 2-3/8" TBG AT 4138.66, POP, P 25 BO & 5 BWPD, 4/14/88