

4 111.5L

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24851-00-00
Spot: SWSENE Sec/Twnshp/Rge: 10-20S-11W
3925 feet from N Section Line, 3100 feet from E Section Line
Lease Name: DOUG PANNING Well #: 5
County: BARTON Total Vertical Depth: 3431 feet

Operator License No.: 32361
Op Name: KREHBIEL, HAL GENE AND ALICE DB
Address: 1219 TURKEY CRK DR
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	313	0	225 SX
T1	2.875	3250		
PROD	5.5	3430	2100	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/25/2010 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 562-8088

Proposed Plugging Method:	Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls. When cutting casing - it jumped like it parted - pulled two joints casing. Ran sandline - went dead at 1800' - will plug from there.
---------------------------	--

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/25/2010 6:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off bottom - topped with 5 sxs cement.
Cut casing at 2100'.
Started plugging at 1800' - tied onto casing and pumped 100 sxs cement with 200# hulls.
Pulled to 920' - pumped 50 sxs cement with 100# hulls.
Pulled to 400' - pumped 150 sxs cement with 100# hulls - circulated cement to surface.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3200	3206		LANSING K

6/10/10
2010061231

RECEIVED
JUN 02 2010
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING-TICKET #37059.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

JUN 02 2010

replacement card

CAT ENERGY LLC
MCPHERSON KS 67460-2829

10-20S-11W
3850' FNL & 3100' FEL, SEC (IRREG)

#5 PANNING, DOUG

site: 1-3/4 S & 1-3/4 E OF ELLINWOOD KS
contr: FORREST ENERGY #3
ged: MIKE HADIX, CONSLT

cty: BARTON
field: CHASE-SILICA

API 15-009-24851

fr date 06/28/2005 spd date 08/16/2005 drig comp 08/25/2005 card issued 03/13/2006 last revised 07/16/2007

	*		

ELV: 1763 KB, 1758 GL LOG	
tops.....	depth/datum
ANH.....	490 +1273
HEEB.....	2680 -917
DOUG.....	2910 -1147
BR LM.....	3002 -1239
LANS.....	3025 -1262
LANS K.....	3190 -1427
BKC.....	3250 -1487
ARB.....	3280 -1517
RTD.....	3429 -1666
LTD.....	3431 -1668

IP status

OIL, LKC 3200-3206 , 02/01/2006
CORR & INFO REL: 7/16/2007 - CORR ELEV (WAS 1755 GL)
& PAY; WAS OIL WELL - TIGHT HOLE
CSG: 8-5/8" 313 / 225 SX (ALT 1), 5-1/2" 3430 / 175 SX
COMMENT: MI & RURT 8/16/2005
NO CORES OR DSTS
TRGT ZN: ARB (OIL), PTD 3500 (ARB), MICT (12/6/2005) -
CO, PF (LANS K) 3200-3206, W / 4 SPF, AC 500 GAL (15%
MA), SWB LD, SO, SET 2-7/8" TBG AT 3250, NO PKR, POP,
OIL WELL (POTENTIAL NOT RPTD), 2/1/2006 - NO OTHER
INFO AVAILABLE

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS