

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-21995-00-00  
Spot: NENWSE Sec/Twnshp/Rge: 22-31S-13W  
2310 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: PARR Well #: 2  
County: BARBER Total Vertical Depth: 4664 feet

\$151.58

Operator License No.: 5205  
Op Name: MID-CONTINENT ENERGY CORP.  
Address: 105 S BROADWAY STE 360  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4400		WITH 2 SX CMT
SURF	8.625	329		WITH 220 SX CMT
PROD	4.5	4661	2700	WITH 300 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/18/2010 8:30 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGERNSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4400' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/18/2010 12:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SET CIBP @ 4400' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

6/10/10  
2010061233

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 09 2010

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Stephen J Pfeifer  
(TECHNICIAN)

RECEIVED

MAY 27 2010

KCC DODGE CITY

Form CR-23