

105.79

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-19234-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 20-33S-3E  
2322 feet from S Section Line, 4930 feet from E Section Line  
Lease Name: WEST RAINBOW BEND UNIT Well #: 8  
County: COWLEY Total Vertical Depth: 3255 feet

Operator License No.: 33608  
Op Name: W.D. SHORT OIL CO., LLC  
Address: 102 S RIVER RD PO BOX 729  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.625	3030	400	100 SX
PROD	5.188	3225	400	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/11/2010 1:00 PM  
Plug Co. License No.: 33608 Plug Co. Name: W.D. SHORT OIL CO., LLC  
Proposal Rcvd. from: MIKE ANSTINE Company: W D SHORT OIL CO Phone: (620) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/12/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3110', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL, 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 3050'. CUT CASINGS @ 400', LAYED DOWN 6.625" CASING AND 400' 5.1875 CASING. RIH W/20' OF 6.625" CASING. RIH W/TBG @ 360', CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 575 SXS 60.40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM, 4-12-2010. CONSOLIDATED CEMENT TICKET #24113.

Perfs:

Top	Bot	Thru	Comments
3225	3255	OH	BARTELSVILLE

6/10/10  
2010061236

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 09 2010  
KANSAS CORPORATION COMMISSION  
WICHITA, KS

Remarks:  
Plugged through: TBG

District: 02 Signed Duane Krueger  
(TECHNICIAN)

JK