

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19235-00-00
Spot: NWSWNWNW Sec/Twnshp/Rge: 20-33S-3E
4507 feet from S Section Line, 5049 feet from E Section Line
Lease Name: WEST RAINBOW BEND UNIT Well #: 10
County: COWLEY Total Vertical Depth: 3264 feet

\$ 106.08

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	271		250 SX
PROD	5.5	3256	1280	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/26/2010 8:00 AM
Plug Co. License No.: 33608 Plug Co. Name: W.D. SHORT OIL CO., LLC
Proposal Rcvd. from: MIKE ANSTINE Company: W D SHORT OIL CO. Phone: (620) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/27/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:
RIH W/TBG @ 1650', CONSOLIDATED MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL. 3% CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 1500'. CUT CASING @ 1280', LAYED DOWN 5-1/2" CASING. RIH W/TBG @ 350', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 225 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM, 4-27-2010. CONSOLIDATED CEMENT TICKET #24395.

Perfs:

Top	Bot	Thru	Comments
3256	3264	OH	BARTELSVILLE

6/10/10
2010061236

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 09 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: OUTSIDE CASIG W/PARTED TBG @ 1547', 690' RODS LEFT IN TUBING
Plugged through: TBG

District: 02 Signed Duane Krueger
(TECHNICIAN)

14