

4 060091

6-3

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 199-20,191-00-00  
40' N of  
SE SE SE, SEC. 13, T 12 S, R 38 W/EX

370 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6926

Lease Name Summers Farm Well # 1

Operator: Advantage Resources

County Wallace 168.55

Name & Address 1775 Sherman, Suite 1345

Well Total Depth 4940 feet

Denver, CO 80203

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 359

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXXXXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. License Number 6033

Address Wichita, KS

Company to plug at: Hour: 10:00AM Day: 3 Month: June Year: 19 90

Plugging proposal received from Dan Mecham

(company name) Murfin Drilling Co. (phone) 316-267-3241

were: Order 190 sxs. 60/40 pos 6% gel and 1/2 #flocel per sx.

Space all plugs with heavy drill mud through drill pipe.

06-07-1990

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXXXXX

Operations Completed: Hour: 10:00AM Day: 3 Month: June Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2535' with 25 sxs. Anhydrite 2519-2548'

2nd plug at 1625' with 100 sxs. Dakota 1323-1623'

3rd plug at 410' with 40 sxs. Surface pipe to 359'

4th plug at 40' with 10 sxs. wiper plug at 40'

rathole with 15 sxs.

Remarks: Allied Cementing

(If additional description is necessary, use BACK of this form.)

~~XXXXXX~~ (do not) observe this plugging.

DATE 6-12-90

INV. NO. 28409

Herb S.  
SEP 14 1990

Signed [Signature]  
(TECHNICIAN)

Herb Deines