

7-24

6 070-35

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 199-20,176 -00-00  
C SE NE, SEC. 34, T 12 S, R 39 W/EKX

TECHNICIAN'S PLUGGING REPORT

Operator License # 3578

3300 feet from S section line

660 feet from E section line

Operator: Medallion Petroleum Inc.

Lease Name Grund Well # 34-1

Name & Address

County Wallace 162.50

2000 Mid Continent Tower

Well Total Depth 5000 feet

401 S. Boston

Conductor Pipe: Size 0 feet

Tulsa, Ok. 74103

Surface Casing: Size 8 5/8 feet 390

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A x \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 N. Water #300 Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 22 Month: July Year: 19 89

Plugging proposal received from Ed McCenna

(company name) Murfin Drilling Inc. (phone) 918-582-4445

were: 8 5/8" - 390' S.P. cwc w/200 sks cement. By Allied Cementing Co.

Narrow well, Elv. 3414' Anhy 2680' No circulation problems. Mud condition 54 vis.

9.1 weight - 9.4 water loss. Proposal 215 sks 60/40 poz 6% gel 3% cal cl. Spot with

drill stem; circulate; heavy mud between all plugs. 30 sks at 2690' - 100 sks w/1 f.c.

50 sks at 440' - 10 sks at 40'. 15 sks in rathole. 10 sks in mousehole.

Plugging Proposal Received by *MJS* Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None \_\_\_\_\_ x 08-01-1989

Operations Completed: Hour: 2:00AM Day: 24 Month: July Year: 19 89

ACTUAL PLUGGING REPORT Murfin ordered 215 sks 60/40 poz 6% gel

3% cal cl. 1 sk f.c. and 8 5/8" plug. Spotted with drill stem. Heavy mud between all plugs.

1st plug at 2690' w/30 sks cement. 15 sks in rat hole

2nd plug at 1680' w/100 sks cement w/1 sk f.c. 10 sks in mousehole.

3rd plug at 440' w/50 sks cement.

4th plug at 40' w/plug and 10 sks cement.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby agree to serve this plugging.

DATE 8-4-89

INV. NO. 25535

7-24

*File S,*

Signed *Marion J. Schmidt*  
Marion J. Schmidt (TECHNICIAN)