

11-16

160  
TJ

062546

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-20,205-00-00

SW NE /4 SEC. 23, 12 S, 41 W  
1980 feet from S section line  
1980 feet from E section line

Operator license# 30575

Lease Burk well #23-1

Operator: Holden Energy Corporation

County Wallace

Address: Lincoln Center - Suite 600  
Armore, OK 73401  
405-226-3960

Well total depth 5240 feet  
Conductor pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 271 feet  
w/165 sks.

170.30

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Emphasis Oil Company License#     

Address: Russell, Kansas 67665

Company to plug at: Hour: 4:45 P.M Day: 12 Month: November Year: 91

Plugging proposal received from: D. L. Finney

Company: Emphasis Oil Company Phone: 405-226-3960

Work: Order 200 sks. 60/40 posmix - 6% gel. - 3% cal. cl. -  
1 sk. flo-cel and 8 5/8" plug. Spot with drill pipe with no less  
than 36 vis. mud between all plugs, with good circulation and no  
fluid loss.

Set pipe 5 1/2".

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All   , Part   , None X

Completed: Hour: 5:00 A.M. Day: 16 Month: November Year: 91

Actual plugging report:

- 1st. plug @ 2850' with 25 sks.
- 2nd. plug @ 1975' with 100 sks. - 1 sk. flocele.
- 3rd. plug @ 300' with 40 sks.
- 4th. plug @ 40' with 10 sks.
- 15 sks. in Rathole.
- 10 sks. in Mousehole.

NOV 25 1991  
11-25-1991

Remarks: Cemented by: Halliburton.

I      observe the plugging.

*Gilbert G. Scheck*

INVOICED

DATE 12-5-91  
33959

(agent)  
Form 09-2/3