

12-26

6 118695

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 199-20,183-00-00

NE SW NE, SEC. 1, T 12 S, R 42 W/E
3780 feet from S section line
1400 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Westfield Well # 1

Operator: Anadarko Pet. Corp
Name & Address: Box 351
Liberal, Ks. 67901

County Wallace 165.17
Well Total Depth 5082 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 359

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling License Number 6033

Address Wichita, Ks.

Company to plug at: Hour: 6:00 PM Day: 26 Month: Dec Year: 19 89

Plugging proposal received from Jim Barlow

(company name) Murfin (phone) _____

were: Order 190 sks cement 60/40 poz 6% gel and 2 sks f.c.
Heavy mud between all plugs.
Pump cement down drill pipe.

Elevation 3696 Anhydrite 2901 - 2950 Arb. No.
Top Dakota 1900

Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6:00PM Day: 26 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT
25 sks at 2930'
100 sks at 2100'
40 sks at 400'
10 sks at 40'
15 sks in rathole

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1990
01-17-1990

Remarks: B. I. Titan Cementing
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Dale F. Balchazor (TECHNICIAN)

DATE JAN 24 1990
INV. NO. 27082

FEB 28 1990 MAR 29 1990