

WELL PLUGGING RECORD


STATE OF KANSAS
STATE CORPORATION COMMISSION

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Russell County. Sec. 33 Twp. 11 Rge. 13W
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. C NW 1/4
Lease Owner. Duwe & Farris
Lease Name. Boxberger Well No. 1
Office Address. 709 Brown Bldg. Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole
Date well completed. 11-15-43 19.
Application for plugging filed. 8-10-45 19.
Application for plugging approved. 8-10-45 19.
Plugging commenced. 8-5-45 19.
Plugging completed. 8-5-45 19.
Reason for abandonment of well or producing formation. Dry Hole



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production. Dry Hole 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. H. W. Kerr
Producing formation. Depth to top. Bottom. Total Depth of Well. 3211 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

The hole was plugged back 3211 ft. to 3060' rock and cement. Heavy mud 3060' to bridge at 130' cement 130 to 100 ft., 15 sacks. Mud 100' to 15' cement into base of cellar, 10 sacks. 130' of 8 5/8 pipe cemented and left in hole.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Duwe & Farris
Address. 709 Brown Bldg. Wichita Ks.

STATE OF Kansas, COUNTY OF Sedgewick, ss. L. A. Harris (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Duwe + Farris

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of March, 1948.

Offie J. Goote Notary Public.

My commission expires April 23, 1949.

PLUGGING
FILE 33-11-R-13W
BOOK PAGE 77 LINE 44

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas


15-167-05077-0000

Company - DUWE & FARRIS
 Farm - Boxberger No. 1.

SEC. 33 T. 11 R. 13 W
 NWc NW

Total Depth. 3211'
 Comm. 10-16-43 Comp. 11-15-43
 Shot or Treated.
 Contractor. Three-Way Drlg. Co.
 Issued. 2-12-44

County. Russell
 KANSAS



CASING:
 8 1/4" 130' Cem.
 5 1/2" 3063' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

shale	70
shale & shells	275
red rock	350
red rock & shale	865
anhydrite	910
red bed, shells	1100
shale & shells	1250
salt	1460
shale & lime	1755
shale	1799
lime	1819
shale & lime	1885
shale	1896
shale & lime	1970
cherty lime	1990
shaly lime	2037
shale & lime	2305
shale	2380
lime	2410
shale & lime	2450
red bed	2475
shale	2509
lime	2560
shale & lime	2740
shale & shells	2779
lime	2872
shale	2888
lime	2950
shale	2955
lime	3045
shale	3052
lime	3060
shale	3065
lime	3105
shale	3110
lime	3145
shale	3160
lime	3206
shale	3211
Total Depth.	



PLUGGING
 FILE SEC 33 T 11 R 13 W
 BOOK PAGE 22 LINE 44