

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-169-20,296-00-00

LEASE NAME Vaupel

WELL NUMBER #1

SPOT LOCATION 3630' FSL & 3630' FEL

SEC. 8 TWP. 13 RGE. 1W (E) or (W)

COUNTY Saline

Date Well Completed 3/13/88

Plugging Commenced 3/13/88

Plugging Completed 3/13/88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR EXCALIBUR PRODUCTION CO., INC.
 ADDRESS P.O. Box 278, McPherson, Ks. 67460

PHONE # 016-241-1250 OPERATORS LICENSE NO. 5330

Character of Well _____
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filled? _____ If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put In	Pulled out
Dirf & Clay		0	20	8 5/8"	20'	None
Sand		20	80	8 5/8"	60'	None
Shale		80	133	8 5/8"	133'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Cemented at 310' with 60 sacks of cement. Cemented at 40' with 10 sacks of cement. 15 sacks in rathole. Plugging completed at 1:30 P. M., March 13, 1988. Plugging completed by Wichita State Corporation Commission office.

(If additional description is necessary, use BACK of this form)

Name of Plugging Contractor Blackstone Drilling, Inc. License No. 59993
 Address P.O. Box 1184, McPherson, Ks. 67460

RECEIVED
 CORPORATION COMMISSION
 03-16-1988
 MAR 16 1988
 CORPORATION DIVISION
 Wichita, Kansas

STATE OF Kansas COUNTY OF McPherson, ss.

Excalibur Production Co., Inc. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) BY: Juanita Flood
Sec. Treas.
 (Address) P.O. Box 78, McPherson, Ks. 67460

SUBSCRIBED AND SWORN TO before me this 15th day of March, 1988

Johnnie L. Schmidt
 Notary Public

My Commission expires: _____

JOHNNIE L. SCHMIDT
 Notary Public
 My Comm. Exp. June 23, 1989

FORM CP-4 1-84
 Revised 06-83



Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

March 14, 1988

15-169-2096-00-00

COMPANY: EXCALIBUR PRODUCTION CO., INC.
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: VAUPEL #1
 LOCATION: 3630' FSL & 3630' FEL NW/4
 Section 8-13-1W,
 Saline County, Kansas
 COMMENCED: March 7, 1988
 COMPLETED: March 13, 1988
 ELEVATION: 1181 K. B.

0	to	20	Dirt & Clay
20	to	80	Sand
80	to	220	Shale
220	to	585	Shale & Lime
585	to	780	Lime & Shale
780	to	1440	Shale & Lime
1440	to	1700	Lime & Shale
1700	to	1903	Shale & Lime
1903	to	2305	Lime & Shale
2305	to	2457	Shale & Lime
2457	to	2655	Mississippi
2655	to	2701	Lime
2701	to	2728	Kindershook Shale
2728	to	2818	Shale
2818	to	2940	Shale & Lime
2940	to	2984	Lime
2984	to	3079	Maquoketa Shale
3079	to	3092	Viola
		3092	T. D.

Cut 12 1/4 hole to 213' and run 215' of 8 5/8" casing, cemented with 150 sacks of cement at 213'. Plug down at 12:30 P. M., March 7, 1988. Hole dry and abandoned. Cemented at 310' with 60 sacks of cement. Cemented at 40' with 16 sacks of cement, 15 sacks in rathole. Plugging completed at 1:30 P. M., March 13, 1988 with the Wichita State Corporation Commission Office.

TOPS:

Measurements taken from K. B.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 16 1988
 03-16-1988
 CONSERVATION DIVISION
 Wichita, Kansas

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and forgoing is a true and correct copy of log on your Vaupel #1, located on the 3630' FSL & 3630' FEL NW/4 Section 8-13-1W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

P. E. Plouffe
 P. E. PLOUFFE, PRESIDENT

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 15th day of March, 1988.

Josephine L. Schmidt
 JOSEPHINE L. SCHMIDT - NOTARY PUBLIC

1988