

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Saline County, Sec. 28 Twp. 13 Rge. 1W (E) (W)

Location as "NE/CNW/SW" or footage from lines _____
Lease Own: W.J. Nelson - Geo. Gore,
Lease Name Gore Well No. 1
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole.
Date well completed April 30 1964
Application for plugging filed April 30 1964
Application for plugging approved April 30 1964
Plugging commenced 8:45 p.m. April 30, 1964
Plugging completed 11:00 " 1964
Reason for abandonment of well or producing formation Dry hole.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Kansas.
Producing formation Viola Depth to top _____ Bottom _____ Total Depth of Well 3200 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
25-80'	Water.					
		0	180	8 5/8"	180	None, 120S ¹ .Cm.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

None filled with heavy mud.
Plug - Brush & 1/2 sx. hulls pushed to 180' with drill pipe.
20 sx. cement placed on plug.
Place heavy mud on plug to within 30' of surface.
Plug at 30'. 1/2 sx. hulls. Place 9 sx. cement on plug, to surface.
Place plug in rat hole - 2 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1965

05-24-1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight & Wise Drg. Co; Inc.
Address Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Saline, ss.
W.J. Nelson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

NEW ADDRESS Walter J Nelson
2072 MARC 2080 Edward St; Salina, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 1965

My commission expires March 3, 1969

Jacqueline C. Nelson
Jacqueline C. Nelson Notary Public.

15-169-00233-00

Drillers Log.

Well: Gore #1.

Location: Sec/ 28- T13-R1W, Saline Co; Kansas.

Operator: W.J. Nelson, Salina, Kansas. Geo. Gore.

Contractor: Knight & Wise Drg. Co; Inc.

Date Started: April 16, 1964.

Date Completed: April 30, 1964.

Casing: 180' - 8 5/8". Dry hole.

0 - 25'	Surface sand & shale.
25 - 80	Sand & shale.
80 - 100	Lime & shale.
100 - 200	Lime & shale.
200 - 240	Gyp. lime, & shale.
240 - 360	Lime & shale.
360 - 800	Shale & lime.
800 - 1105	Shale & sand.
1105 - 1400	Shale & shells.
1400 - 1620	Shale & lime.
1620 - 2380	Lime & shale.
2380 - 2510	Shale, lime & sand.
2510 - 2588	Shale & lime.
2588 - 2592	Chert.
2592 - 2735	Lime, shale & chert.
2735 - 2902	Lime, shale.
2902 - 2935	Shale & lime.
2935 - 2960	Sand & lime.
2960 - 3050	Lime, shale & sand.
3050 - 3160	Shale & lime.
3160 - 3185	Shale.
3185 - 3200	Lime.
3200	T.D.

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1965
05-24-1965
CONSERVATION DIVISION
Wichita, Kansas