

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
 412 Union National Bk. Bldg., Wichita, Kansas

15-169-0050-00-00


Company - PRYOR & LOCKHART, INC.
 Farm - Duncan No. 1.

SEC. 35 T. 13 R. 1 W
 SEc SE

Total Depth. 3307'
 Comm. 12-10-43
 Shot or Treated.
 Contractor.
 Issued. 3-25-44

Comp. 2-12-44

County. Saline
 KANSAS



CASING:
 10" 101' Cem.
 7" 2443'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

gravel & shale	55	Tops:	
shale & shells	101	Base Miss.	2702
lime	190	Hunton	2848
lime & shale	220	Sylvan Shale	2990
lime	242	Viola	3090
lime brkn	340	Simpson	3200
lime & shale	835	Simpson Sand	3240
shale & brkn sand	927	Arbuckle	3275
shale & shells	1085		
shale & lime	1225		
shale & shells	1390		
lime & shale	1485		
lime	1680		
lime & shale	1814		
lime	1950		
shale & lime	1980		
lime	2018		
shale & lime	2078		
lime	2122		
lime & shale	2420		
shale & shells	2442		
dolomite	2444		
sand	2452		
lime	2492		
lime sdy	2494		
lime, chert, flint	2504		
lime	2702		
lime & shale	2843		
shale	2845		
lime	2852		
lime & shale	2880		
lime	2990		
shale Sylvan	3009		
shale	3092		
lime	3102		
lime & chert	3120		
lime	3216		
lime & shale	3250		
lime & sand	3260		
lime & shale	3270		
Arbuckle lime	3307		
Total Depth.			

150 rocks
 5 collar
 10-02-1944

A few sand clusters
 slight stain, not
 saturated, good
 porosity 2442
 Sand highly
 stained 2444

35 13 1 W
 123 1

Perf. 12 shots 2442-37 $\frac{1}{2}$
 Perf. 10 shots 2437 $\frac{1}{2}$ -35
 Perf. 12 shots 2431 $\frac{1}{2}$ -35