

11-2 4-010311

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-109-20,659-00-00

N2 SW NW /4 SEC. 36, 12 S, 35 W  
1650 feet from S section line  
660 feet from E section line

Operator license# 6113

Lease: Berndt Well # 1-36

Operator: Landmark Energy Exploration

County: Logan 153,47

Address: 1861 N. Rock Road - #205  
Wichita, Kansas 67206

Well total depth 4722 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 300 feet

Aband. oil well Gas well, Input well, SWD, D & A X

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 2 Month: November Year: 1997

Plugging proposal received from: Greg Davidson

Company: L.D. Drilling, Inc. Phone: -

Were: Space all plugs with heavy drilling mud through drill pipe.  
Used 60/40 pozmix - 6% gel with 1/4# flocele per sack.

11-05-1997

Plugging Proposal Received by: Case Morris

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 2:45 P.M., Day: 2, Month: November, Year: 1997

Actual plugging report:

- 1st. Plug at 2550' with 25 sxs.
- 2nd. Plug at 1400' with 100 sxs.
- 3rd. Plug at 350' with 40 sxs.
- 4th. Plug at 40' with 10 sxs.
- Rathole with 15 sxs.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: GL

I did[ ] / did not[ X] observe the plugging.

Case Morris  
(agent)

Form CP-2/3

100

INVOICED

DATE 11-14-97

INV. NO. 49506