

6010164

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-199-20052-00-00

NW, SEC. 9, T. 12 S, R. 38 W

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5706

Lease Name Carol G. Sweet Well # 22-9

Operator: First Energy Corp.

County Wallace

Name & Address 16701 Greens Point

Well Total Depth 5793 188.27 feet

Suite 200

Conductor Pipe: Size \_\_\_\_\_ feet

Houston Texas 77060

Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilg Co. License Number 6033

Address Wichita Ks.

Company to plug at: Hour: PM Day: 6 Month: 7 Year: 19 84

Plugging proposal received from Bill Reiter

(company name) Murfin Drilg. (phone) 913-462-7541

were: order 220 sx. cement 50/50 permix 6% gel. 3% c.c.

1-5x hulls 1.8 5/8 plug 1 sx flow seal

Heavy mud between all plugs

Pump cement down drill pipe.

Elev. 3280 Anhydrite 2580-2614 Arbuckle. 5520

Dakota 1900 Plugging Proposal Received by Walter F. Balthazor  
1380 = 1680 (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None (circled)

Operations Completed: Hour: 2:30 AM Day: 18 Month: 7 Year: 19 84

RECEIVED  
STATE CORPORATION COMMISSION

ACTUAL PLUGGING REPORT circulated @ 5520 for 30 mi.

25 SX @ 5520

25 SX @ 2600

100 SX @ 1680 mixed with 1sx flow seal

40 SX @ 390 dumped 1sx hulls, pushed plug to 40'

10 SX @ 40

Remarks: 10SX Rot Hole cementing Co. Sun  
(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging: 10SX mouse hole

Lost 179' of 4 1/2 Drift. Pipe in the hole cemented in with 100SX com.

Signed Walter F. Balthazor (TECHNICIAN)

July 20 21