

6 020168

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-199-20,058-00-00

SE NE NE, SEC. 9, T 12 S, R 38 W/E

4290 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7506

Lease Name Richard Garvey Well # 82-9

Operator: First Energy

County Wallace

Name & Address 16701 Greenpoint Park Dr.

Well Total Depth 4900 159.25 feet

Suite 20

Conductor Pipe: Size 0 feet

Houston, Tx 77060

Surface Casing: Size 8 5/8 feet 344

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 6030

Address Box 288, Russell, Ks.

Company to plug at: Hour: AM Day: 26 Month: September Year: 19 84

Plugging proposal received from Terry McRay

(company name) Murfin (phone) \_\_\_\_\_

were: Order 200 sks 50/50 pozmix 6% gel 3% cal. cl., 2 sks cello-flake and 8 5/8" plug.

Spot drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11 AM Day: 26 Month: September Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 2650 w/30 sks

2nd plug @ 1710 w/100 sks and 2 sks cello-flake

3rd plug @ 350 w/40 sks

4th plug @ 40 w/10 sks Bridge

10 sks in Rat Hole and 10 sks in Mouse Hole

Remarks: Cemented by Sun

(If additional description is necessary, use BACK of this form.)

I (~~did~~ / did not) observe this plugging.

Signed Gilbert Ballthaus (TECHNICIAN) 9-28-84

INVOICED  
DATE 10-5-84  
INV. NO. 4047  
9-26 NOV 7 1984