

4-010439

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-167-22,086 -0000

E2 E2 SW /4 SEC. 30, 11 S, 12 W
1330 feet from S section line
2970 feet from E section line

2/2

\$98.64

Operator license# 5184
Operator: Shields Oil Producers
Address: Sheilds Building
Russell, Kansas 67665

Lease: Hegarty Well# 2
County: Russell
Well total depth 3035 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 449 feet

Aband. oil well Gas well , Input well , SWD , D & A

Plugging contractor: Quality Well Service License# -

Address: _____

Company to plug at: Hour: 9:00 A.M. Day: 2 Month: February Year: 2000

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service Phone: -

Were: _____

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 11:00 A.M., Day: 2, Month: February, Year: 2000

Actual plugging report: Sanded to 2906' and dumped 4 sxs cement. Shot off casing at 2046'. Pulled to 1325' and pumped 65 sxs 60/40 pozmix - 10% gel cement with 250# hulls. Pulled to 750' and pumped 40 sxs cement with 150# hulls. Pulled to 225' and circulated with 40 sxs cement and 100# hulls.

Remarks: _____

Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did[] / did not[] observe the plugging. Cor Moun

INVOICED
2/14/00
061243

102

RECEIVED
(agent) STATE CORPORATION COMMISSION
Form CP-273

R

FEB 11 2000

CONSERVATION DIVISION
Wichita, Kansas