

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-167-22,232-0000

NW 1/4 SEC. 33, T 11 S, R 14 W

2310 FEET FROM N/8 SECTION LINE

2310 FEET FROM W/8 SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5146

LEASE NAME Stielow D Well # 1

OPERATOR: Rains & Williamson Oil Co., Inc  
NAME & ADDRESS: 435 Page Court  
220 West Douglas  
Wichita, Kansas 67202

COUNTY Russell

WELL TOTAL DEPTH 3440 111.80 FEET

CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET

SURFACE CASING: SIZE 8 5/8" FEET 258'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A X

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR Rains & Williamson Oil Comp, Inc LICENSE NUMBER 5146

ADDRESS SAME

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YEAR: 19

PLUGGING PROPOSAL RECEIVED FROM Larry Hinderlichter

(COMPANY NAME) Rains & Williamson (PHONE) \_\_\_\_\_

WERE: 1st plug @ 3440' with 20 sacks

2nd " " 900' " 20 "

3rd " " 500' " 80 " & 1sx celloflake

4th " " 290' " 40 "

5th " " 40' " solid bridge plug & 10 sx

Rathole - 10sx PLUGGING PROPOSAL RECEIVED BY \_\_\_\_\_ (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL \_\_\_\_\_ PART \_\_\_\_\_ NONE X

OPERATIONS COMPLETED: HOUR: 12:00pm DAY: 17 MONTH: Jan YEAR: 1984

ACTUAL PLUGGING REPORT \_\_\_\_\_

order 180 sx 50/50 posmix, 4% gel, 3% CC

REMARKS: Elevation 1821 KB, Anhydrite depth 899-934'

did penetrate Anbuckle, cemented by Haliburton / Allid

I (DID / DID NOT) OBSERVE THIS PLUGGING.

SIGNED David Korman (TECHNICIAN)

2-8-84  
0132

RECEIVED  
STATE CORPORATION COMMISSION  
2-6-84  
FEB 06 1984

FORM CP-2/3  
REV. 6-83