

10-24

6 070726

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 167-22,610-0000

NE NE, SE SEC. 34, T 11 S, R 14 W/E

feet from S section line

feet from E section line

Lease Name John Fuller Well # 2

County Russell

Well Total Depth ~~3320~~ 3230' feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 338

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Operator: Name & Address Rains and Williamson Oil
435 Page Ct. 220 W. Douglas Inc.
Wichita, Kansas 67202

Paul Stephens

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Co. Tools and B. J. Titan License Number

Address Wichita, Ks. and Hays, Ks. 67601

Company to plug at: Hour: 9:00AM Day: 24 Month: Oct Year: 19 88

Plugging proposal received from Gerald Ptachek

(company name) Rains and Williamson Inc. (phone)

were: 8 5/8" - 338' S.P. cwc w/235 sks. 5 1/2" casing set at 3229' w/150 sks. Perfs

2942' - 2978'; at bottom sand to 2890' w/5 sks cement. Shot csg twice recovered

1300'; ran in wireline to 300'; obstruction. Proposal: Run tubing to

825'. Circulate w/cmt and squeeze. Proposal 200 sks 60/40 Poz 6% Gels

Hulls.

RECEIVED
STATE CORPORATION COMMISSION
12-29-88

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:00PM Day: 24 Month: Oct Year: 19 88

CONSERVATION DIVISION
Wichita, Kansas
88

ACTUAL PLUGGING REPORT Ordered 200 sks 60/40 Poz 6% Gel and 5 sks Hulls.

Ran tubing to 825' and circulated with 200 sks cement. Returned for another

50 sks cement. 500 psig. Cemented by B. J. Titan, Hays, Ks.

Remarks: (If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Marion J. Schmidt (TECHNICIAN)

INVOICED
DATE 1-6-89
INV. NO. 23520