

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-167-22,029-0600

NW, Sec. 34, T 11 S, R 14 WE

2310 feet from N/W section line

330 feet from W/W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Steinle Well # 5

Operator: Thunderbird Drilling Co.  
Name & Address Box 18407, Wichita, Ks. 67218

County Russell

Well Total Depth 3540 feet \$123.90

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Thunderbird Drilling Co. License Number 38

Address Box 18407, Wichita, Ks. 67218

Company to plug at: Hour: 5:00 PM Day: 14 Month: 2 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Ed Cook

(company name) Thunderbird Drilling Co. (phone) 316-685-1441

were: Order 160 lbs. 50 premix - 4% gel. - 3% Col. Cl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3540' w/ 20 sh. 2nd plug C 825' w/ 80 sh. 3rd plug C 400' w/ 40 sh. 4th plug - solid bridge of hulls & plug C 40' w/ 10 sh. Circulate 10 sh. in rat hole.

Signed G. L. Schell  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:00 PM Day: 14 Month: 2 Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 370' sl. cas. w/ 260 sh. cement 2% gel. - 3% Col. Cl.

Ordered 160 lbs. 50 premix - 4% gel. - 3% Col. Cl. & 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3540' w/ 20 sh. 2nd plug C 825' w/ 80 sh. 3rd plug C 400' w/ 40 sh. 4th plug - solid bridge of hulls & plug C 40' w/ 10 sh. Circulated 10 sh. in rat hole.

Remarks: \_\_\_\_\_

STATE CORPORATION COMMISSION

3-14-83  
MAR 14 1983

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~/ did not) observe this plugging.

Signed G. L. Schell  
(TECHNICIAN)

INVOICED

DATE 3-30-83  
INV. NO. 811-W

FORM CP-2/3  
Rev. 9-82