



AUG 15 1973

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1973
08-15-1973
CONSERVATION DIVISION
Wichita, Kansas

15-109-20025-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Eike Mickelson of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Mickelson guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Medford Well No. 1

Location: CHW-SE Sec. 7 Twp. 12 Rge. (E)(W) 36

County: Logan Total Depth 4707' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Mickelson was instructed to plug the well as follows:

169'--8 5/8" Surface casing, cement circulated with 135 Sx.
Top of Dakota section @ 1250'.

Circulate hole with heavy mud. Pull DP to 1475' and displace 110 Cu. Ft. cement thru DP. Pull DP to 180' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 140' with sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

A. L. Dickels
Conservation Division Agent