



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
7-21-72  
JUL 21 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ed Weiler of Shields Drilling Company has this date requested permission to plug the following described well:

Mr. D. R. Wyckoff guarantees payment of the plugging fee.

Operator's full Name: R. D. Wyckoff

Complete Address: 121 S. 5th., Osborne, Kansas

Lease Name: Wyckoff Well No. # 1

Location: NW NE SE Sec. 33 Twp. 11 Rge. 13 (E)(W) W

County: Russell Total Depth 3120 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Ed Weiler was instructed to plug the well as follows:

8 5/8" csg. 224' Cwc.

Circulated hole with heavy mud to 480', set plug, & displaced 50 sax cement thru drill pipe. Mud to 220' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Allied Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

[Signature]  
Conservation Division Agent