

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

8-3-67  
AUG 3 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. E. T. Drube of M. J. Bove Operating Co. has this date requested permission to plug the following described well:

Mr. E. T. Drube guarantees payment of the plugging fee.

Operator's full Name: M. J. Bove Operating Company

Complete Address: 754 E. Wichita Ave., Russell, Kansas 67665

Lease Name: Gillette Well No. # 2

Location: SW SE NE Sec. 33 Twp. 11 Rge. 13 (E)(W) W

County Russell Total Depth 3800 Oil Well

Gas Well  Input Well  SWD Well X D & A  Lost Hole

Mr. Bob Barnes was instructed to plug the well as follows:

8 5/8" 152' Cwc. Perf. 3090'

Sanded hole back to 3000' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 15 sax mud & 100 sax cement with

Allied Cementing Company's pump truck, cementing from 320' to base

of cellar.

Very truly yours,

Don L. Linn  
Conservation Division Agent