



15-169-20028-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

December 3, 1969

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 8 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
12-08-1969

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Pat Plouffe of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Plouffe guarantees payment of the plugging fee.

Operator's full Name: Walters Drilling Company

Complete Address: 400 Insurance Bldg., Wichita, Kansas 67202

Lease Name: Tobin Estate Well No. 1

Location: C SW NW Sec. 17 Twp. 13 Rge. 1 ~~(E)~~ (W) X

County: Saline Total Depth 3145' Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. Plouffe was instructed to plug the well as follows:

Fill hole with mud to 180'. Push plug and 1/4 sack hulls to 180' and  
cement hole with 25 sacks cement through drill pipe. Fill hole with  
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10  
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent