

1-27

6 110703

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 199-20,187-00-00
SW SW SE, SEC. 30, T 12S, R 42 W/E
487 feet from S section line
2013 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417
Operator: Union Pacific Res. Co.
Name & Address: Box 7 MS 3407
Fort Worth, Tx. 76101

Lease Name Pauline Well # 34-30
County Wallace 172-25
Well Total Depth 5300 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 537

Abandoned Oil Well Gas Well Input Well SWD Well D&A XX

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling License Number
Address Wichita, Ks.

Company to plug at: Hour: Day: 27 Month: 1 Year: 19 90

Plugging proposal received from Bobby Cooper

(company name) Murfin Drilling (phone)

were: Order 225 sks cement 60/40 poz 6% gel and 2 sks f.c.
Heavy mud between all plugs.

Pump cement down drill pipe.

Elevation 3848 Anhydrite 2938 - 70 Arb. No.
Top Dakota 1975

Plugging Proposal Received by D.F.B. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XX

Operations Completed: Hour: 4:30 AM Day: 27 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT
25 sks at 2960'
100 sks at 2170
40 sks at 560'
10 sks at 40'
15 sks in rathole 10 sks in mousehole

Remarks: B. J. Titan Cementing
(If additional description is needed, use BACK of this form.)

INVOICED
DATE 2-16-90
INV. NO. 27480

RECEIVED
FEB 14 1990
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
Signed

Dale F. Balthazor
(TECHNICIAN)

Dale F. Balthazor
FORM CP-2/3
Rev. 01-84

Jils
APR 17 1990