

12-28

6 041118

167-01,705 - 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

ME NE SW, SEC. 9, T 11 S, R 15 W/4E

2310 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6854

Lease Name Chrisler B Well # 2

Operator: B. P. Exploration I c.

County Russell 112.61

Name & Address Box 37

Well Total Depth 3465 feet

Gorham, Ks. 67640

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 101' w/100 sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____

Address Hays, Ks. 67601

Company to plug at: Hour: 9:00AM Day: 28 Month: Dec Year: 19 89

Plugging proposal received from Joel Stull

(company name) B. P. Exp Inc. (phone) _____

were: 7" at 3453' w/150 sks; BV at 1060' circ to surface w/400 sks.

Perfs at 3092' - 3316' T.O.C. 2800' (CBL)

Ordered _____ sks 65/35 poz 8% gel 2% cc and 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 6:10PM Day: 28 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Set EZSV at 3000': sq 100 sks cement w/3 sks hulls.

at 300# psi to plug bottom. Spot gel to 1000'; 15 sks gel. Pull tubing to 1100'

and circ 135 sks cement to surface; pulled tubing and hooked up to 7" casing;

pumped add 10 sks cement w/300# s.i. annulus sq to surface from 1060' w/400 sks.

RECEIVED
STATE CORPORATION COMMISSION
1-17-90
JAN 17 1990

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 24 1990

INV. NO. 27086

John S.

Signed Dennis L. Hamel (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas