

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20234-00-02  
Spot: NWSENE Sec/Twnshp/Rge: 15-14S-21W  
3375 feet from S Section Line, 752 feet from E Section Line  
Lease Name: LECUYER Well #: 1  
County: TREGO Total Vertical Depth: 1430 feet

Operator License No.: 31627  
Op Name: WHITETAIL CRUDE, INC  
Address: PO BOX 544 N HWY 283  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	209	0	w/175 sxs cmt
PROD	5.5	1430	0	w/400 sxs cmt

Well Type: SWD UIC Docket No: D23673.0 Date/Time to Plug: 06/08/2010 8:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIKE J. FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 06/08/2010 9:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Ran tubing to 1140' and pumped 105 sxs cement with 200# hulls - circulated.  
POOH.  
Topped off with 25 sxs cement.  
Max. P.S.I. 500#.

6/21/10  
2010061268

Remarks: SWIFT CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

RECEIVED

JUN 15 2010

JUN 11 2010

SABRE EXPLORATION  
WICHITA KS 67202

15-14S-21W  
C SE NE

# 1 LECUYER OWWO

site: 6-1/2 S & 3-3/4 W OF ELLIS KS	city: TREGO	API 15-195-20234-A
contr: WHEATSTATE OILFIELD SVC	field: SUNNY SLOPE NORTH EXT	
geol: MATT TOTTEN	(1/4 N)	
fr date 05/25/84	drig comp 06/20/84	card issued 01/31/85
spd date 06/20/84		last revised 01/20/97

				A

ELV: 2199 KB LOG

tops.....	depth/datum
ANH.....	1567 + 632
TOP.....	3270 -1071
HEEB.....	3517 -1318
LANS.....	3556 -1357
BKC.....	3805 -1606
MARM.....	3890 -1691
CONG CHT.....	3960 -1761
ARB.....	4028 -1829
RTD OLD.....	4065 -1866
LTD OLD.....	4069 -1870

**IP status**  
**SWDW, CED HILL 1148-1166, 01/04/85.**  
 INFO REL: 1/20/97 - WAS SWDW - TIGHT HOLE  
 NOTE: CORR 1/4/73 - CORR ARB TOP (WAS 3828-1829)  
**OLD INFO:** OPERATOR WAS MACK OIL CO, 1  
 LECUYER, SPD 08/29/72, 09/05/72 8-5/8" 209 / 175 SX,  
 D&A, ARB, 09/05/72 (CARD ISSUED 10/19/72)  
 CONTR: THOMAS DRILLING  
 GEOL: BENNY SINGLETON  
 NO CORES  
 DST (1) 3611-3645 (LANS), / 30-30-60-30, REC 700' SW,  
 W/SPTS DEAD OIL ISIP 1182# FSIP 1023# IFP 18#  
 FFP 346#

COPYRIGHT 1997  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

SABRE EXPLORATION  
WICHITA KS 67202

15-14S-21W  
C SE NE

# 1 LECUYER OWWO

**NEW INFO:** FR 05/25/84, RE-ENTERED 06/20/84 WSH DWN TO 1430 DC 06/20/84 CSG: SET 5-1/2" 1416 / 400 SX MICT - CO, PF (CED HILL) 1148-1166, COMP AS SWDW - INJECTION RATE SATISFACTORY, 1/4/85