

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20732-00-00

Spot: SWNESW

Sec/Twnshp/Rge: 1-33S-3E

1396 feet from S Section Line, 3720 feet from E Section Line

Lease Name: SHANE

Well #: 3

County: COWLEY

Total Vertical Depth: 3320 feet

Operator License No.: 33405

Op Name: ANSTINE & MUSGROVE INC.

Address: PO BOX 391

PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

SURF	8.625	210		125 SX
------	-------	-----	--	--------

PROD	5.5	3320	605	
------	-----	------	-----	--

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/29/2010 8:00 AM

Plug Co. License No.: 34271

Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.

Proposal Revd. from: GARY ANSTINE

Company: ANSTINE & MUSGROVE INC

Phone: (620) 441-8165

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 04/29/2010 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3200'. DUMP BAILED 5 SXS CEMENT ON TOP. PARTED 5.5" CASING @ 605', LAYED DOWN CASING. RIH W/TBG @ 350', CONSOLIDATED MIXED & PUMPED 177 SXS 60/40 POZMIX 4% GEL. CEMENT CIRCULATED. PLUG DOWN 5:00 PM, 4-29-2010. CONSOLIDATED CEMENT TICKET #24169.

Perfs:

Top	Bot	Thru	Comments
3268	3284	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

RECEIVED

JUN 11 2010

KCC WICHITA