

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20361-00-00  
Spot: NESENE Sec/Twnshp/Rge: 12-33S-3E  
3657 feet from S Section Line, 329 feet from E Section Line  
Lease Name: TREGO Well #: 10  
County: COWLEY Total Vertical Depth: 3250 feet

Operator License No.: 33405  
Op Name: ANSTINE & MUSGROVE INC.  
Address: PO BOX 391  
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211		150 SXS CMT
PROD	5.5	3235	862	150 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/30/2010 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: GARY ANSTINE Company: ANSTINE & MUSGROVE INC Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE  
Date/Time Plugging Completed: 04/30/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 992', CONSOLIDATED MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL, 3& CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 756'. RIH W/TBG @ 350', CONSOLIDATED MIXED & PUMPED 150 SXS 60/40 POZMIX 4% GEL. CEMENT CIRCULATED. PLUG DOWN 5:00 P, 4-30-2010. CONSOLIDATED CEMENT TICKET #24170.

Perfs:

Top	Bot	Thru	Comments
3235	3250	OH	OPEN HOLE

6/11/10  
2010061741

RECEIVED  
JUN 11 2010  
KCC WICHITA

Remarks: 862' OF 5-1/2" CASING HAD BEEN PREVIOUSLY PULLED FROM THIS WELL BEFORE PLUGGING DATE.

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)