

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23871-00-00
Spot: NENWNE Sec/Twnshp/Rge: 9-9S-19W
383 feet from N Section Line, 1806 feet from E Section Line
Lease Name: HOGAN Well #: 1-9
County: ROOKS Total Vertical Depth: 3532 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/08/2010 3:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: AMERICAN WARRIOR, INC. Phone: (620) 275-7461

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL WitnessType: NONE
Date/Time Plugging Completed: 06/08/2010 4:15 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st. Plug at 3440' w/25 sxs.
2nd. Plug at 1465' w/25 sxs.
3rd. Plug at 760' w/100 sxs.
4th. Plug at 270' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

6/21/10
2010061246
RECEIVED
KANSAS CORPORATION COMMISSION

JUN 14 2010

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

CM