

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-30008-00-00  
Spot: NWSENW Sec/Twnshp/Rge: 13-22S-18W  
3630 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: EDDY Well #: 2  
County: PAWNEE Total Vertical Depth: 4294 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1100		WITH 450 SX CMT
PROD	5.5	4272	980	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/11/2010 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: KEVIN FISCHER Company: APOLLO ENERGIES Phone: (620) 672-9001

Proposed Plugging Method: SAND TO 4775' WITH 5 SX CMT. PLUG AT 1130' WITH 15 SX GEL & 50 SX CMT. CIRCULATE CMT FROM 300' TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/11/2010 12:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 3775' WITH 5 SX CMT. 1ST PLUG AT 1130' WITH 16 SX GEL & 50 SX CMT WITH 2% CC. 2ND PLUG CIRCULATE CMT FROM 300' TO SURFACE WITH 100# HULLS & 95 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4079	4116		CHEROKEE
3826	3846		LANSING

6/26/10  
2010061247

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
JUN 14 2010  
KCC DODGE CITY

RECEIVED  
JUN 15 2010  
KCC WICHITA

Form CP-25