

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20511-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 28-32S-29W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: ROLLINS Well #: 2
County: MEADE Total Vertical Depth: 5798 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1470		WITH 750 SX CMT
PROD	4.5	5496	2980	WITH 325 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/03/2010 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 50' ABOVE PERFS & 20 SX CMT. PLUG AT 1550' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/03/2010 3:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

PUMP 200# HULLS & 75 SX CMT. 1ST PLUG AT 1550' WITH 15 SX GEL & 50 SX CMT W/100# HULLS. 2ND PLUG AT 550' WITH 50 SX CMT W/100# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5638	5643		LKC
5624	5632		MORROW
4555	4559		LKC

6/21/10
2010061247

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 14 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed

Jerry W. Stapleton
PIRTE (TECHNICIAN)

RECEIVED

JUN - 9 2010

KCC DODGE CITY

Form CP-2/3