

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-03496-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 1-12S-18W  
1583 feet from S Section Line, 2370 feet from E Section Line  
Lease Name: KARLIN A Well #: 4  
County: ELLIS Total Vertical Depth: 3669 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	128	0	w/75 sxs cmt
PROD	4.5	3681	0	w/125 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/27/2010 9:30 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/27/2010 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3600' - pumped 150 sxs cement with 300# hulls.  
Pulled tubing to 1800' - pumped 75 sxs cement - good circulation of cement.  
Pulled tubing out - tied onto backside - pumped 25 sxs cement. Shut in at 300# P.S.I.  
Filled 4 1/2" with 10 sxs cement - plug job complete.

Perfs:

Top	Bot	Thru	Comments
3384	3656		

6/21/10  
2010061248


RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 14 2010

Remarks: ALLIED CEMENTING COMPANY-TICKET #41603.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

CONSERVATION DIVISION  
WICHITA, KS

JUN 02 2010

GLENN NYE

#4

KARLIN A

1-12-18W  
SW NW SE

34

Contr.

ELLIS

County

E 2110RB

Comm.

Comp.

9-28-51

IP

100 BOPD (ARB)

Tops	Depth	Datum
HEEB	3306	-1196
KC	3348	-1238
CONG	3595	-1485
ARB	3631	-1521
T.D.	3681	-1571

Casing

8" 128 PERF 18 S, 3654=56  
5" 3680 PMP 100 BOPD

BEMIS POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS