

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-25845-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 8-35S-16E
1907 feet from S Section Line, 2494 feet from E Section Line
Lease Name: DECOWS Well #: 1
County: MONTGOMERY Total Vertical Depth: 1300 feet

Operator License No.: 34027
Op Name: CEP MID-CONTINENT LLC
Address: 15 WEST SIXTH ST, STE 1100
TULSA, OK 74119

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1110		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/10/2010 8:00 AM
Plug Co. License No.: 3097 Plug Co. Name: K W OIL WELL SERVICE, INC.
Proposal Rcvd. from: LARRY CASEY Company: CEP MIDCON. Phone: (918) 697-4216

Proposed Plugging Method: Perf well .Run cement string to TD. Circulate Cement to surface

Plugging Proposal Received By: RUSSELL HINE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/11/2010 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Perf well at 500' and 250'. Ran 1" cement string to 1000' and hit bottom. Contractor pumped 102 sacks of cement, but never circulated fluids to the surface. The 1" was pulled and ran back in on 5/11/2010 and cement was tagged at 510'. Cement was pumped and circulated to the surface. The cement string was pulled and well was topped off. Casing was dug out and cut off. 150 sacks of portland was used.

Perfs:

RECEIVED

JUN 10 2010 RHH

KCC Chanute Dist. #3

6/25/10
2012061299

Remarks: 37.01298178 95.68289163

Plugged through: TBG

District: 03

Signed

Russell Hine
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 14 2010

CONSERVATION DIVISION
WICHITA, KS